ValueFilter® Gen 3

Installation Update

ValueFilter® Gen 3 has slightly different dimensions than the previous generation of ValueFilter®.

Standard length 5", 6", and 7" ValueFilter® Gen 3 are intended to be installed at a pitch of 20-23° and will require adequate space between the top of the gutter and the roof line. This will work best on new gutter installations or existing gutters that are hung with sufficient space between the roof line and gutter. The pitch helps ensure that any debris that lands on the gutter guard will slide off or blow off with a slight breeze.

The Stubby versions of ValueFilter® Gen 3 are intended to be installed with an 8° pitch. These guards will work best on new or existing gutters that are hung with less space between the top of the gutter and the roof line.

Please see the schematics below and order accordingly:

